

Noistop[®] Steel

Installation guide

1 First the supports must be placed and potentially supported by a concrete foundation. The supports are to be placed with a distance of 200 cm.



2 The panel is lifted from the side and placed between the supports so that the mounting plates are fitted on the front of the supports.



3 When the panel has been placed along the soil, it is mounted with screws through the holes in the mounting plate - all holes should be used.



4 When the panel has been mounted a joint strip is placed on the top of the panel in all its length, securing a close joint between the panels.



5 When the joint strip has been placed, the next panel is placed on top of the first panel and is mounted in the same way.



6 When the top element has been mounted, the installation is finished. It is important that there are no "gaps" in the joint between panel and soil.



Lapinus, ROCKWOOL B.V., P.O. Box 1160, 6040KD Roermond, The Netherlands
T +31 475 35 35 55 **E** info@lapinus.com **W** lapinus.com/noistop

© ROCKWOOL B.V. 2018. All rights reserved. - Reference: January 2018
ROCKWOOL, Lapinus, Rockdelta and Noistop are registered trademarks of ROCKWOOL International A/S. The information contained herein is based upon data considered to be accurate. However, no warranty is expressed or implied regarding the accuracy of this data or the results that will be obtained from the use thereof, or that any such use will not infringe on any patent. This information is furnished as a guide only and on condition that those receiving it shall carry out appropriate tests to determine the accuracy and suitability for the intended purpose.